

Educational Suitability Summary Report

Maplewood Elementary School

Date: 01/12/2021 Score 56% Average

Maplewood Elementary School, serving an enrollment of approximately 390 students, is in east central Austin. It was built in the 1950s and consists of approximately 45,390 SF. The school is known for incorporating arts into all classes in its curriculum through the Creative Learning Initiative. Maplewood is a dual-language school offering pre-K through fifth grade and offers a variety of activities to students, including an after-school program dedicated to creativity.

The unique architecture of the building allows studios to feel more spacious with the flood of natural light and high ceilings. Most lower grade levels are in the longer studio wing, and most of the upper grade levels are taught in portables. While this assessment does not cover the portables, it is assumed that spaces in portables will be found deficient. Studios lack corridor transparency and collaboration space. The gym is undersized but has great natural lighting. The dining commons area is adequately sized for school's capacity and also has great natural lighting in addition to cultural murals. The library is small, but the librarian has created a maker space in one corner, equipped with a 3D printer. Teachers have created multiple maker contraptions that typically sit in the hallway outside the library for students to play with between classes.

The outdoor areas of the campus are well-thought-out. Gardens are sprinkled all around the back of the campus and a learning pond and butterfly garden mark a central area for the gardens. Spaces in between portables are filled with greenery. The front of the old boiler house (now storage) has been turned in to an outdoor stage area with plenty of seating options.

Interview Overview

Principal Vickie Jacobson invited parents, community members, faculty and staff to join us during the interview. The 1950s building has led to many challenges, but Maplewood has found unique opportunities to overcome them. The most notable areas that everyone commented on are the outdoor spaces. These are places they feel must never change, and the faculty has put a lot of effort into creating space for the students. One of the more creative spaces is the outdoor theater set against the old boiler building, nestled into the topography of the site. Staff mentioned that additional play places for the older students would be beneficial. The back of the campus is filled with portables, which limits available play area.

Educational Suitability Summary Report

Maplewood Elementary School

Arts integration is pivotal to the curriculum at Maplewood. A community arts partnership is set up with each grade level; however, space around the campus does not allow for flexibility. Additional multipurpose learning and collaboration spaces would be helpful.

Teachers requested additional workspaces and a dedicated maker/STEM space was a top wish list item. Teachers and staff have been creative in how they address this need while still providing this programming. The librarian has created a maker corner in the library filled with books, a 3D printer and project space. Teachers also created a maker area in the corridor outside of the library. A recurring theme was that spaces are too small for the enrollment and are not fit for modern learning.

Assessment Findings

The Educational Suitability Assessment of Maplewood Elementary School earned a 56% overall score and places the campus in a category of Average. The assessment consists of seven General Building categories and seven Academic categories to determine areas that need more attention.

Unsatisfactory Categories (36-50%):

Academics and Learning

Score is unsatisfactory.

Studios are an appropriate size but lack adequate storage and have no transparency to the corridor. The building is not set up for learning neighborhoods and does not have small group or collaboration areas or areas to work independently.

General Building

Score is unsatisfactory.

Only one community space is able to allow after-hours functions without access to learning areas. There is no dedicated community room, and the cafeteria or gym are the only areas able to be used. The appearance of the school conveys pride for the students and community.

Security

Score is unsatisfactory.

PE and Wellness

Score is unsatisfactory.

The gym is undersized and needs new flooring. Physical education support spaces are disconnected and across the corridor.

Technology

Score is unsatisfactory.

Chalkboards, markerboards and movable screens are typical throughout studios. Some have a projector and screen. Studios lack enough outlets for technology-driven learning. Charging carts were seen in storage at the time of this assessment. No digital media signage for visitors in the

Perkins&Will

Educational Suitability Summary Report

Maplewood Elementary School

reception area.

Administration Spaces

Score is unsatisfactory.

The large size of the room feels welcoming and has informal seating. Acoustics in admin spaces could use improvement. There is no conference room for public/parent use; this space was converted to an office.

Average Categories (51-65%):

Exterior

Score is average.

Student drop-off happens in the visitor parking lot and has a small queue area. The school provides an overhang for waiting at this location. Bus drop-off happens on the residential street and does not have cover. School signage is on the busier street but is not on the adjacent corner to the main entrance.

Controllability of Systems

Score is average.

Lighting controls are typical two switches controlling alternating rows. The switches are separated in the room, with one switch at the door and one switch on another wall. There are HVAC units near the windows that allow individual control, but teachers said they do not work as intended.

Visual and Performing Arts

Score is average.

Music studio is undersized but offers adequate storage. The stage size is adequate but feels short, making the space seem smaller than it is. There is no stage storage. The art studio was renovated two years ago and has attached storage and a kiln.

Food Services

Score is average.

Dining commons area is very undersized but receives great natural light and has outdoor views. Kitchen and support spaces are undersized and do not have an accessible path to outdoor dumpsters.

Media Resources

Score is average.

Media center is small and does not support quiet study. Part of the room has been converted to the maker space, which reduces area for books or informal seating.

Satisfactory Categories (66-80%):

Outdoor Learning and Activity

Score is satisfactory.

Outdoor areas are vast; however, there are no true outdoor studios. There are garden beds throughout the central outdoor space as well as a learning pond and monarch garden with signage. The school does not have cisterns, nature loop trails or animal husbandry.

Perkins&Will

Educational Suitability Summary Report

Maplewood Elementary School

Environmental Quality

Score is satisfactory.

All studios have access to natural light and views outside. Most studios have operable windows for better controllability of the space. Acoustics and artificial lighting are average in studios. Staff mentioned there have been issues with pests and rodents.

Furniture, Fixtures, Equipment

Score is satisfactory.

Furniture appears age appropriate and some allows rapid reconfiguration, although most appears cumbersome for younger students to move on their own. There is a mix of new and old furniture, and the lower-grade studios have a variety of furniture types.



Student drop-off has a covered waiting area but is not located near the main entrance. Queueing space is limited.



Central outdoor area features a learning pond, butterfly garden and a seating area.



They have converted the old boiler building into the backdrop of the outdoor stage. Outdoor tables and the topography create a lot of seating space.




There are many planter beds in similar condition around this central outdoor space. They appear well-used and tended to and are near a water source.

Maplewood Elementary School



Murals and displays show school pride




Administration Spaces feel welcoming and are adequately sized.

Maplewood Elementary School



Waste collection is clearly presented and labeled in various areas similar to the one shown.



Gym is undersized and the flooring needs renovated. Receives great natural light.

Maplewood Elementary School



Typical Studio: Space is adequately sized but lacks storage space. Studios receive great natural light.



Art studio has plenty of great storage and good natural light. The room appears in newer condition.



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Maplewood Elementary School	Patrick Reinhard and Kendall Claus	1/12/2021

- Exterior		1	2	3	4	5	N/A	1	8.75	60%
1.1 Does the si pedestrian	te permit desirable separation of vehicular, bus and traffic?			3				Comments	1.00	3.00
1 2 3 4	Very unsatisfactory - Bus, car and pedestrian all happen at the same location Unsatisfactory - Cars and buses mix, pedestrians are separated Average - Buses, cars, and pedestrians are separate but stack space is small Satisfactory - Buses, cars, and pedestrians are separate but drop off does not have a canopy or a holding place like a commons or cafeteria Very satisfactory - Buses, cars, and pedestrians are separate and drop off area has a canopy and destination							Drop-off and pickup happen through staff parking, we specially in the morning. Bus pickup and drop-off ho School has tried to get city to change east street to or asked for more parking, but have not been successful	ippen on north ie-way and ho	n side. ave
N/A	Does not apply									
12 Is the build	ling easily identified with appropriate signage and vayfinding?			3				Comments	0.25	0.7
1	Very unsatisfactory - Campus has no signage / wayfinding	ı						Sign is on busier street, but is not on the adjacent correntrance.	ner to the mair	า
2 3 4 5	Unsatisfactory - Signage/wayfinding is faded/hidden Average - Signage / wayfinding visible but not apparent Satisfactory - Signage / wayfinding is visible but not good condition Very satisfactory - Signage and wayfinding is visible							Principal's comment: It is not clear to the public that the school is on the corner of Ashwood and Maplewood. or signage at the front door.		
N/A	and easy to use Does not apply									

O2/11/2022 ²

1 - E	exterior (co	nt.)	1	2	3	4	5	N/A	4		
1.3	Is the dump	oster accessible for trash / compost disposal?			3				Comments	0.50	1.50
	1 2 3 4 5	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster Unsatisfactory - Compost is present. Route has obstacles to dumpster Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent. Satisfactory - Compost and dumpster are directly adjacent and route is barrier free Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped							Adjacent to kitchen but not easily accessible from the tricky during lunch hours. Principal's comment: No access to trash and compost Custodian must take trash through the kitchen to acce	from the cafe	teria.
		/ positioned so people of all heights can access it.									
	N/A	Does not apply									
2 - 0		arning and Activity	1	2	3	4	5	N/A	1	15.00	73%
2.1	Are outdoo the ed spec	or studios and support spaces appropriately configured per :?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No dedicated outdoor studios							No true outdoor studio, only outdoor seating areas.		
	2	Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no shade provided									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area									
	4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area									
	5	Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area									
	N/A	Does not apply									
2.2		playgrounds (elementary only) and support spaces per the ed spec?				4			Comments	1.00	4.00
	1	Very unsatisfactory - No dedicated active playground		•	•	•			Playground and playcourt both have shade structures) .	
	2	Unsatisfactory - Too small, poor condition, no shade									
	3	provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or									
	4	less shade coverage over play structure Satisfactory - Good size, good condition, more than 50% shade coverage over play structure									
	5	Very satisfactory - Generous size, excellent condition, full shade coverage over play structure									
	NI/A	Dogg not apply									

2 - 0	Outdoor Le	arning and Activity (cont)	1	2	3	4	5	N/A	4		
2.3	Are garden spec? (eval	is and support spaces appropriately configured per the ed uation on infrastructure not condition of plants)				4			Comments	0.00	0.00
	1 2 3 4 5	Very unsatisfactory - No dedicated gardens Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source Average - Adequate size, adequate condition, needs some renovations or updates to function well, water source is difficult to access Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation							Monitoring answer, does not affect the score for Out-Activity. There are several garden beds. Unclear as to any, during a normal school year. There are hose spig central beds.	which are use	ed, if
2.4	N/A Are the rained spec?	Does not apply n gardens and/or cisterns appropriately configured per the	1						Comments	0.00	0.00
	1 2 3 4 5	Very unsatisfactory - No rain gardens or cisterns Unsatisfactory - Too small, poor condition, not functioning, disconnected Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well Satisfactory - Good size, good condition, functions properly Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided				Monitoring answer, does not affect the score for Outdoor Learning and Activity. Principal's comment: Poor drainage and erosion down the hill from the courtyard. Rain garden were put in by parents and staff in the courtyard. Rain washes through the basement area under the foundation of the 2nd wing.					the tyard.
2.5	N/A	Does not apply chool have animal husbandry? (optional)	1						Comments	0.00	0.00
2.5	1 5	No Yes	ı						Comments Maybe at one point. There is an old chicken coop.	0.00	0.00
2.6		hool have nature loop trails? (optional)	1						Comments	0.00	0.00
	1 5	No Yes									
2.7		thool have a learning pond? (optional)					5		Comments	0.00	0.00
	1	No									
2.8	5 Does the so	Yes chool have a grass play field and walking trail?					5		Comments	1.00	5.00
	1 5	No Yes							,		

3 - General Bu	illding	1	2	3	4	5	N/A		11.25	47%
	r circulation routes wide enough to safely and effectively date student movement?				4			Comments	0.50	2.00
3.1 accommod 1 2 3 4 5 N/A	Very unsatisfactory - Primary circulation is 5'-0" to 6'-0" wide Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide Average - Primary circulation is 7'-0" to 8'-0" wide Satisfactory - Primary circulation is 8'-0"-10'-0" wide Very satisfactory - Primary circulation is 10'-0"+ wide Does not apply unity use areas arranged so that the school can allow night without full school access? Very unsatisfactory - Cafeteria, gym, and library cannot be accessed after hours Unsatisfactory - Only one of the public spaces (Cafeteria, Gym and Library) can be accessed from parking and secured after hours Average - Only two of the public spaces can be accessed from parking and secured after hours		2		4			Comments Comments The addition of the lift in one of the corridors makes i close anymore. Otherwise, gym and library could be completely secure. The cafeteria does not have direct	0.75 t so security go used after-hou	1.50 ate can't
5	Satisfactory - All of the public spaces can be accessed from parking and secured from the rest of the building but not individually Very satisfactory - Cafeteria, gym, and library can be accessed from parking and locked off from rest of campus for night/evening use with their own entrance									
N/A	Does not apply					1				
3.3 Is there a constraint of school for	community room that is a dedicated meeting space outside unction?	1						Comments	0.75	0.75
1 2 3 4 5	Very unsatisfactory - No dedicated community room Unsatisfactory - Community room but within school function, no access after school hours Average - Community room, moderate size, but need some renovations or updates to function well Satisfactory - Community room, good size /layout, meets needs /functions well Very Satisfactory - Community room, generous size, nice condition, functions appropriately outside of school function Does not apply									
Does the a	eneral appearance of the school convey pride for the					l				
	nd community?				4			Comments	0.25	1.00
1 2 3 4 5	Very unsatisfactory - General appearance is poor Unsatisfactory - General appearance is aged but ok Average - General appearance is good Satisfactory - General appearance shows pride in campus and student works Very Unsatisfactory - General appearance shows pride in campus and student works and is welcoming to the community							Principal's comment - Murals are a school tradition a of the school/culture	nd part of the	history
N/A	Does not apply									

4 - Security	1 2 3 4	5 N/A	·	16.25	
4.1 Does the facility have key card access at all major entries?			Comments	0.25	_
1 Very unsatisfactory - No entries					
2 Unsatisfactory - 1/4 of major entries					
3 Average - 1/2 of major entries					
4 Satisfactory - 3/4 of major entries					
5 Very satisfactory - All of major entries					
N/A Does not apply			T		
4.2 How adequate is site lighting and security for the campus overall?			Comments	1.00	
Very unsatisfactory - No exterior lighting, no secure perimeter					
2 Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal					
Average - Lighting at all night-use entries and parking lot, but poor condition. Security is moderate					
4 Satisfactory - Lighting at all night-use entries and					
parking lots, good condition, signage less visible,					
perimeter is well secured but needs updates					
Very satisfactory - Signage, parking lots, and entries are well lit, visible and easy to use, perimeter is very secure					
N/A Does not apply					
Is the main office located at the school entry and configured with a			Comments		
4.3 secure vestibule to the main corridor?			Comments	1.00	
1 Very unsatisfactory - No secure vestibule, office located					
far from main entry, allows visitors access to school					
unsupervised 2 Unsatisfactory - No secure vestibule, office located					
somewhat far from main entry, minimal supervision of					
visitors					
3 Average - Office close to entry, views of front door, but					
no secure vestibule					
4 Satisfactory - Office is well-located with a secure					
vestibule, but needs updates 5 Very satisfactory - Office well-located with secure					
very satisfactory - Office well-located with secure vestibule and all appropriate security features					
N/A Does not apply					
Is there enough interior transparency for faculty to passively supervise	el l				
4.4 learners and their activities who are not in studios?	2		Comments	1.00	2.00
1 Very unsatisfactory - No transparency of walls	_		Small windows in doors.		
2 Unsatisfactory - Limited transparency in certain location	s				
3 Average - Good transparency in certain locations but					
inadequate or missing in other locations of school					
4 Satisfactory - Adequate transparency throughout the					
school 5 Very satisfactory - Excellent transparency throughout th					
school	5				
N/A Does not apply					
• • •					

Perkins&Will 02/11/2022 ⁶

!	5 - Environmental Quality	1	2	3	4	5	N/A		25.00	76%
	5.1 How are acoustics in studios in general?			3				Comments	1.00	3.00
	1 Very unsatisfactory - Recognized word/sound from adjacent studio/corridor 2 Unsatisfactory - Audible sound from adjacent studio/corridor 3 Average - Slight sound from outside room 4 Satisfactory - Walls to deck insulated only white noise from mechanical system 5 Very satisfactory - Able to hear quiet speaking from across the room N/A Does not apply									
	5.2 Is the studio artificial lighting adequate quality?			3				Comments	1.00	3.00
	 Very unsatisfactory - Sporadic lights work, glare, less than 20 FC Unsatisfactory - 10-19 FC or serious glare Average- 20-29 FC minor glare Satisfactory - 30-39 FC and no glare Very satisfactory - 40+ FC and no glare 									
	N/A Does not apply									
	5.3 Is there access to natural light in studios?					5		Comments	1.00	5.00
	1 Very unsatisfactory - No learning spaces have natural light 2 Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light 3 Average - 26-50% of learning spaces have natural light batisfactory - 51-75% of learning spaces nave natural light 5 Very satisfactory - 76-100% of learning spaces have natural light							Operable windows in most.		
	N/A Does not apply		1	ı		I				
	5.4 Is there access to outside views from learning spaces?					5		Comments	1.00	5.00
	1 Very unsatisfactory - No learning spaces have views 2 Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out 3 Average - 26-50% of learning spaces have views 4 Satisfactory - 51-75% of learning spaces have views 5 Very satisfactory - 76-100% of learning spaces have views N/A Does not apply									

5 - Environme	ntal Quality (cont.)	1	2	3	4	5	N/A	4		
5.5 Does the b	ouilding have odor or pest problems?			3				Comments	1.00	3.00
1	Very unsatisfactory - Evidence of both pests and odors						•	Limited evidence, but staff mentioned ant problems, c	ockroaches a	nd rats.
2	Unsatisfactory - Evidence of pests or odors							·		
3	Average - Limited evidence of pests, no odors									
4	Satisfactory - No evidence of pests / odors, school									
	cleanliness in good condition									
5	Very Satisfactory - No evidence, school cleanliness in									
	excellent condition									
N/A	Does not apply									
6 - Controllab	ility of Systems	1	2	3	4	5	N/A	\ \	12.50	52%
6.1 Does the s	tudio thermostat allow for individual control?	1						Comments	0.50	0.50
1	No							Principal's comment: due to high ceilings in classrooms	s, ceiling fans	would
5	Yes							help to circulate air and provide cooling		
6.2 Are shade:	s provided to control natural light in learning spaces?				4			Comments	1.00	4.00
1	Very unsatisfactory - No, windows are covered with							Blinds are provided - they seem to be in average cond	lition	
	boards/paper									
2	Unsatisfactory - No, windows have no light control									
3	Average - Yes, but poor condition blinds									
4	Satisfactory - Yes, blinds									
5	Very satisfactory - Blackout shades									
N/A	Does not apply									
6.3 What is the	e quality of lighting controls in the studios?		2					Comments	1.00	2.00
1	Very unsatisfactory - Single switch only per room							2 switches provided in studios. 1 switch at the door and	d 1 switch is in	the
2	Unsatisfactory - Alternating rows switch off							back near the storage.		
3	Average - Alternating lamps in single fixtures switch off									
4	Satisfactory - Tri level switching									
5	Very satisfactory - Dimmable									
N/A	Does not apply									

7 - Fu	urniture, F	ixtures & Equipment	1	2	3	4	5	N/A		18.75	69%
7.1	What is the	current condition of the furniture?				4			Comments	0.75	3.00
	1 2 3 4 5	Very unsatisfactory - Damaged or broken, non- functioning Unsatisfactory - Torn/ bent/ wrong size Average - Scratched/dented/marked Satisfactory - Not new, but sturdy and clean Very satisfactory - New				•		•	Principal's comment: Some flexible seating has been classrooms using grant funds that teachers have app		some
	N/A	Does not apply									
7.2		ty of furniture types being accommodated throughout the arning commons, dining commons, other multi-use spaces?			3				Comments	1.00	3.00
	1	Very Unsatisfactory - Same furniture used in all spaces			•	•		•	Library and the pre-K/kindergarten studios have a ve	ariety of furnitu	re
	2	Unsatisfactory - Furniture variety in one multi-use space							types.		
	3 4 5 N/A	Average - Furniture variety in more than one multi-use space Satisfactory - All multi-use spaces have greater than one type of furniture Very satisfactory - All multi-use spaces have greater than two types of furniture Does not apply									
7.3	How well do	oes furniture accommodate rapid reconfiguration of a			3				Comments	1.00	3.00
	1 2 3 4 5 N/A	Very Unsatisfactory - Furniture is fixed or very heavy Unsatisfactory - Furniture does not allow desks to be configured as individuals, small groups, or large groups Average - Mix of furniture that can reconfigure but is cumbersome to move Satisfactory - Furniture is flexible for multiple configurations of space Very satisfactory - Furniture is flexible for multiple configurations of space, easy to move and stack							Some allows rapid reconfiguration, although most a for younger students to move on their own.	ppears cumber	some
7.4		Does not apply ure ergonomic and size appropriate for grade level?				4			Comments		
7.4	1 2 3 4 5	Very unsatisfactory - Desk with attached chair combinations too small for grade level Unsatisfactory - Desk with attached chair combinations Average - Mix of studios with tables/loose chairs and desks with fixed seats Very satisfactory - Tables with loose chairs Very satisfactory - Tables with loose chairs that allow							Comments	1.00	4.00
	N/A	students to be active Does not apply									

Perkins&Will 02/11/2022 ⁹

Waste	1	2	3	4	5	N/A		5.00	100
Do studios and corridors have blue recycle bins with bilingual instructions and/or image sorting instructions?					5		Comments	0.50	2
1 Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. 2 Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. 3 Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage. 4 Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage. 5 Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus. N/A Does not apply							A score for this category is being recorded, but this co-calculated in the overall ESA average.	ategory is not	
Does the cafeteria (or wherever meals are served) have at least one of each: green compost bin, blue recycle bin, and landfill bin? Are the bins labelled clearly with bilingual and/or image sorting?					5		Comments	0.50	
 Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage. Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent. 							A score for this category is being recorded, but this co calculated in the overall ESA average.		
Average- There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent.									
 Satisfactory- There are several waste stations as described above Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting. 									



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

Academics - Elementary School

School Name	Walk Attendees:	Date:
Maplewood Elementary School	Patrick Reinhard and Kendall Claus	1/12/2021

8 - Aca	demics	& Learning	1	2	3	4	5	N/A	A	65.00	38%
8.1 Ar	re studios	appropriately configured per the ed spec?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility,							Size appropriate; however, there is a lack of transpar	ency to corrido	or, small
		disconnected							door connection to other studio, and not enough stor	age, limiting fl	exibility
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected							of teaching methods.		
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.									
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces									
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces									
	N/A	Does not apply									
27		nd Kinder have appropriate support spaces such as and storage per the ed spec?			3				Comments	1.00	3.00
	1	Very unsatisfactory - None provided							Yes to restrooms, no to storage.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent condition									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ²

8 - A	Academics (& Learning (cont.)	1	2	3	4	5	N/A	4		
8.3		have appropriate support spaces such as storage per the			3				Comments		
0.0	ed spec?				0				Comments	1.00	3.00
	1	Very unsatisfactory - None provided							Not enough storage.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
	4	updates or renovations to function well Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
	3	condition									
	N/A	Does not apply									
	•	earning neighborhoods have small group rooms and open		l I			l	1		I	
8.4	collaboration		1						Comments	1.00	1.00
	1	Very unsatisfactory - No breakout rooms or open		<u> </u>				<u> </u>		1.00	1.00
	'	collaboration spaces are provided									
	2	Unsatisfactory - Too small or too few, poor condition, no									
	2	flexibility, lacks visual connection to learning									
		neighborhood, poor acoustic privacy									
	3	Average - Adequate size, adequate condition, needs									
	J	some renovations or updates to function well									
	4	Satisfactory - Good size, good condition and flexibility,									
	•	transparency and connection to learning neighborhood,									
		acoustic privacy									
	5	Very Satisfactory - Generous size, excellent condition									
	· ·	and flexibility, transparency and connection to learning									
		neighborhood, acoustic privacy									
	N/A	Does not apply									
	•	I studios large enough to support project-based learning									
8.5		le teaching modalities?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility, does not		l .			l				
		support project-based learning									
	2	Unsatisfactory - Undersized, decentralized resources,									
		limited flexibility									
	3	Average - Adequate size, needs some renovations or									
		updates to function well									
	4	Satisfactory - Good size, centralized resources, good									
		flexibility									
	5	Very Satisfactory - Generous size, centralized project									
		resources, excellent flexibility									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ³

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A	4		
8.6		Spaces and support spaces appropriately configured per		2					Comments		
0.0	the ed spec			_						1.00	2.00
	1	Very unsatisfactory - No dedicated maker spaces							Currently in library. Not very big.		
	2	Unsatisfactory - Too small, poor condition, disconnected									
	•	from learning spaces, no flexibility									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected to									
	•	learning spaces									
	5	Very Satisfactory - Generous size, excellent condition,									
		connected to learning spaces									
	N/A	Does not apply									
8.7	Is there a Pr	rofessional Learning Center in the learning neighborhood?	1						Comments	1.00	1.00
	1	Very unsatisfactory - No dedicated space for		1							
		Professional Learning Center									
	2	Unsatisfactory - Too small, poor condition, disconnected									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected									
	5	Very Satisfactory - Generous size, excellent condition,									
	NI/A	connected									
	N/A	Does not apply						ı	T		
8.8	Is there a de	edicated science room and support space?	1						Comments	0.00	0.00
	1	No							Monitoring answer, but doesn't affect overall score.	0.00	0.00
	5	Yes							anower, successive arrest everall score.		
	Are there a	dequate places to display the evidence and artifacts of									
8.9		oth 2D and 3D)?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No dedicated space							2D tackable space in corridors		
	2	Unsatisfactory - Too small, non-dedicated, poor									
		condition									
	3	Average - Adequate size, adequate condition, needs									
	4	updates or renovations to function well									
	4 5	Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition									
	D/A	Does not apply									

Perkins&Will 02/11/2022 ⁴

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A			
8.10	Does the bu	uilding provide adequate opportunities for		2					Comments		
8.10	students/te	achers to collaborate in varying group sizes?							Comments	1.00	2.00
	1	Very unsatisfactory - No space to support collaboration							Only available areas are dining commons, library or	outdoors.	
		in various sizes.									
	2	Unsatisfactory - Too small, inflexible, only one option,									
		does not support a variety of group sizes									
	3	Average - Adequate space for collaboration, needs									
		updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, multiple									
	_	options to support a variety of group sizes									
	5	Very Satisfactory - Generous size, excellent condition,									
	N1/A	multiple options to support a variety of group sizes									
	N/A	Does not apply		1		1			T		
8.11	Does the bu	uilding provide opportunities for informal interaction?	1								
	1	Very unsatisfactory - No space					•				
	2	Unsatisfactory - Too small, poor condition, layout and									
		furnishings do not support informal interaction well									
	3	Average - Adequate size and condition, needs updates									
		or renovations to function well.									
	4	Satisfactory - Good size, good condition, layout and									
	_	furnishings support informal interactions									
	5	Very Satisfactory - Generous size, excellent condition,									
	NI/A	layout and furnishings support informal interactions									
	N/A	Does not apply		l	ı	ı				1	
8.12		arning neighborhood / building provide adequate es for students to work independently?	1						Comments	1.00	100
	opportuniti				<u> </u>	<u> </u>				1.00	1.00
	ļ	Very unsatisfactory - No breakout rooms/small study									
	2	spaces Unsatisfactory - Too small, poor condition, no acoustic									
	2	privacy, only one space for independent work,									
		disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates									
	3	or renovations to function well.									
	4	Satisfactory - Good size and condition, acoustic privacy,									
		variety of independent work space options, connected to									
		learning neighborhood									
	5	Very Satisfactory - Generous size, excellent condition,									
		acoustic privacy, variety of independent work space									
		options, connected to learning neighborhood									
	N/A	Does not apply							•		

Perkins&Will 02/11/2022 ⁵

8 - A	cademics	& Learning (cont.)							
8.13	•	Education spaces appropriately configured per the ed	1				Comments		
	spec?						33	1.00	1.00
	1	Very unsatisfactory - Too small, no flexibility,					In portables.		
		disconnected							
	2	Unsatisfactory - Too small, only one area for all teaching							
		methods, limited flexibility, disconnected							
	3	Neutral - Adequate size, multiple areas for different							
		teaching methods, adequate flexibility, limited							
		transparency and connection to other studios and							
		shared learning spaces, needs updates or renovations to							
	4	function well. Satisfactory - Good size, multiple areas for different							
	4	teaching methods, good flexibility, good transparency							
		and connection to other studios and shared learning							
		spaces							
	5	Very Satisfactory - Generous size, multiple areas for							
		different teaching methods, excellent flexibility,							
		generous display area and visual teaching tools,							
		excellent transparency and connection with other							
		studios and shared learning spaces							
	N/A	Does not apply							
8.14	•	Education support spaces, such as storage, space for	1				Comments		
0.14	washer/dry	ver, appropriately configured per the ed spec?	ட்				Comments	1.00	1.00
	1	Very unsatisfactory - None provided							
	2	Unsatisfactory - Too small, disconnected, poor condition							
	3	Neutral - Adequate size, average condition, needs							
		updates or renovations to function well							
	4	Satisfactory - Good size, connected, good condition							
	5	Very Satisfactory - Generous size, connected, excellent							
		condition							
	N/A	Does not apply							
8.15	Are Accessi	ble restrooms and changing rooms readily available to the	1				Comments		
0.15	Special Edu	ucation spaces?					Comments	1.00	1.00
	1	No							
	5	Yes							

Perkins&Will 02/11/2022 ⁶

9 - Visual and	Performing Arts	1	2	3	4	5	N/A	4	15.00	60%
9.1 Are music per the ed	spaces and the cafeteria stage appropriately configured spec?		2					Comments	1.00	2.00
1 2 3	Very unsatisfactory - Too small, missing program spaces Unsatisfactory - Too small, poor condition Neutral - Adequate size, adequate condition, needs							Music room is undersized; separated from performan short, but adequate SF.	ce stage. Stag	je is
4 5	updates or renovations to function well. Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition							Stage lighting is not sufficient for performances. Sour antiquated.	nd system is	
N/A	Does not apply		ı	ı	1	1		,		
9.2 Are music per the ed	and performance storage spaces appropriately configured spec?			3				Comments	1.00	3.00
1 2	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition							Music office is currently being used for storage. There the stage.	e is also no sto	rage for
3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent condition									
N/A	Does not apply	1								
9.3 Are Visual ed spec?	Arts spaces and storage appropriately configured per the				4			Comments	1.00	4.00
1	Very unsatisfactory - Too small, missing program spaces							New storage spaces. Art room was renovated 3 years	ago.	
2	Unsatisfactory - Too small, poor condition									
3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									

Perkins&Will 02/11/2022 ⁷

10 - PE and We	ellness	1	2	3	4	5	N/	A 10.0	00 40%
10.1 Does the co	ampus meet the ed spec standard for physical education paces?		2					Comments 1.0	00 2.00
1 2 3 4 5 N/A	Very unsatisfactory - Too small, missing program spaces Unsatisfactory - Too small, poor condition Average - Adequate size, adequate condition, needs some renovations or updates to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply				•			Needs to be larger and needs new floor. Storage is disconnect hallway. A/V was present. Principal's note: PE teacher added wall mounted equipment (climbing net, climbing rope).	
10.2 Are the phy	vsical education storage spaces appropriately configured spec?		2					Comments 1.0	00 2.00
1 2 3 4 5 N/A	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition Neutral - Adequate size, average condition, needs updates or renovations to function well Satisfactory - Good size, connected, good condition Very Satisfactory - Generous size, connected, excellent condition Does not apply					,		Across hallway. Storage space is not adequate and has hot w installed in space that does not currently work.	ater heater
11 - Food Service		1	2	3	4	5	N/	A 10.0	00 60%
11.1 Is the Dining	g Commons appropriately configured per the ed spec?			3				Comments 1.0	3.00
1 2	Very unsatisfactory - Too small, missing program spaces Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation	l			1			A little small but great natural light. School's capacity is 355 recafeteria sized at 2,010 SF. Current cafeteria is 2,400 SF; hower enrollment is 390 requiring a cafeteria 2,200.	
3	Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space)							Principal noted that they cannot accommodate current enroll an extended lunch period. Sound transmission is also an issue	
5 N/A	Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply								
	od Services support spaces appropriately configured per			3				Comments 1.0	00 3.00
1 2 3 4 5	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition Neutral - Adequate size, average condition, needs updates or renovations to function well Satisfactory - Good size, connected, good condition Very Satisfactory - Generous size, connected, excellent condition				•			Could be larger for ease of function according to cafeteria sto	ff.
N/A	Does not apply								

12 - Media Res	ources	1	2	3	4	5	N/A	4	30.00	57%
12 1	ry/Media Center easily accessible for the occupants and			3				Comments		
visitors to tl	he school?			O				Comments	1.00	3.00
1	Very unsatisfactory - Not accessible							Far from reception and main entrance. No clear way	finding. Door to	0
2	Unsatisfactory - Limited access, difficult to find, no							outside.		
	transparency									
3	Average - Adequate accessibility, needs updates or									
	renovations to function well									
4	Satisfactory - Accessible, easy to find, good									
	transparency, good condition									
5	Very Satisfactory - Accessible, easy to find, excellent									
21/4	transparency, excellent condition									
N/A	Does not apply	1	1	1	ı	1	1			
12.2 How well d	oes the Library/Media Center support quiet study?		2					Comments	1.00	2.00
1	Very unsatisfactory - No quiet study spaces							Two small rooms adjacent to library are used for store	age, office, and	d work
2	Unsatisfactory - One area in poor condition, poor							rooms.		
	acoustic privacy									
3	Average - One or more areas provided, needing									
	updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
-	center, good condition, good acoustic privacy									
5	Very Satisfactory - Multiple clusters or small rooms									
	adjacent to media center, excellent condition, excellent									
N/A	acoustic privacy Does not apply									
		l	l	1	1		l			
12.3 How well d	oes the Library/Media Center support social interaction?			3				Comments	1.00	3.00
1	Very unsatisfactory - No space							From assessment walk, the library felt pretty open.		
2	Unsatisfactory - Too small, poor condition, layout and									
	furnishings do not support informal interaction well							Principal's note: Too sectioned off for meetings or add	eauate social	
3	Average - Adequate size and condition, needs updates							interaction.		
	or renovations to function well.									
4	Satisfactory - Good size, good condition, layout and									
	furnishings support informal interactions									
5	Very Satisfactory - Generous size, excellent condition,									
	layout and furnishings support informal interactions									
N/A	Does not apply	1	1	1	1		1			
12/1	oes the Library/Media Center support collaborative work pups (4-8 students)?		2					Comments	1.00	2.00
1	Very unsatisfactory - No breakout rooms, no flexible							Principal's comment: Not enough shelf space and wo	rk spaces.	
	furniture, no support								·	
2	Unsatisfactory - Too small, one area, poor condition									
3	Average - Adequate size, multiple areas provided,									
	needing updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
	center, flexible furniture, good condition									
5	Very Satisfactory - Multiple clusters or small rooms									
	adjacent to media center, flexible furniture, excellent									
	condition									
N/A	Does not apply									

	12 - Media Res	ources - Continued	1	2	3	4	5	N/A	4		
	12.5 How well do	pes the Library/Media Center support collaborative work				4			Community		
	in larger gro	oups (10-25)?				4			Comments	1.00	4.0
	1	Very unsatisfactory - No gathering areas							Stadium reading area and movable tables and chairs.		
	2	Unsatisfactory - Too small, one common space, limited									
		seating, poor condition									
	3	Average - Adequate size, one common space, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, multiple common spaces with									
		seating, good condition									
	5	Very Satisfactory - Generous size, multiple commons									
		spaces with seating, excellent condition									
	N/A	Does not apply									
	12.6 How well do	pes the Library/Media Center support technology?			3				Comments		
	12.0 110W Well do	ses the Library, Media center support technology.)				Comments	1.00	3.00
	1	Very unsatisfactory - No vis comm tools							TV and projector/screen.		
	2	Unsatisfactory - Outdated, poorly functioning, or									
		insufficient									
	3	Good - Mix of old and new whiteboards/projectors/etc.									
	4	Satisfactory - Projectors, marker boards, smart boards in									
		most spaces - good condition									
	5	Very Satisfactory - Projectors, marker boards, smart									
		boards in most spaces - new condition									
	N/A	Does not apply									
	13 - Technology	/	1	2	3	4	5	N/A	Ą	20.00	50%
	13.1 How well ed	quipped are the facilities with instructional technology?			3				Comments		
						<u> </u>	<u> </u>	<u> </u>		1.00	3.00
	1	Very unsatisfactory - Limited to no technology present in							Typical movable screens. Some have projectors.		
		instructional spaces									
	2	Unsatisfactory - One type of technology present									
	3	Average - Multiple types of technology, smart boards,									
		poor condition, limited to only certain areas of school									
	4	Satisfactory - Multiple types of technology, smart									
		boards, good condition.									
	5	Very Satisfactory - Multiple types of technology, smart									
		boards, excellent condition									
	N/A	Does not apply					1	1			
	13.2	adequate number of power and data outlets in learning		2			1	1	Comments	100	
	spaces?	V				1	1	1		1.00	2.00
	1	Very unsatisfactory - Outlet configuration does not									
	0	support digital devices throughout school (1 per wall)									
	2	Unsatisfactory - Outlet configuration support digital									
	2	devices only in certain areas of school (2 per wall) Average - Outlet configuration support digital devices									
	S										
	4	but not enough capacity throughout school (3 per wall)									
	4	Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity									
		throughout school (>3 per wall)									
	5										
	3	Very Satisfactory - Excellent outlet configuration to support digital devices throughout school (>3 per wall)									
		support glaital devices throughout school (>3 per wall)									
Į	N/A	Does not apply									

02/11/2022 ¹⁰

I3 - Technolog	yy (cont.)	1	2	3	3 4		5	N/A			
13.3 Are there o	adequate charging locations for devices?		2						Comments	1.00	2.0
1	Very unsatisfactory - No centralized charging location										
2	Unsatisfactory - Centralized charging location, but										
	inadequate in size for number of devices										
3	Average - Charging cart or tower but not adequately sized for number of devices										
4	Satisfactory - Charging cart or tower not centralized										
5	Very Satisfactory - Charging cart or tower located										
	centralized location. Excellent condition										
N/A	Does not apply										
3.4 Is there ad	equate AV for presentations spaces – cafeteria and gym?			3	3				Comments	1.00	3.0
1	Very unsatisfactory - AV not present in one or more								Present but could be better.		
	space										
2	Unsatisfactory - AV undersized for room, poor condition										
3	Average - Adequately sized / poor condition OR AV										
	undersized / adequate condition										
4	Satisfactory - Good size, good condition										
5	Very Satisfactory - Generous sized, excellent condition							Ĺ			
N/A	Does not apply		ı		1	1	1	1			
13.5 Is there dig	gital media signage at the reception area?	1							Comments	0.00	0.0
1	Very unsatisfactory - No digital media present in				ı	-					
	reception area										
2	Unsatisfactory - Undersized, poor condition										
3	Average - Adequately sized / poor condition OR undersized / adequate condition										
4	Satisfactory - Media signage present, good sized, good										
ĺ	condition										
5	Very Satisfactory - Generously sized, excellent condition										
N/A	Does not apply							ļ			

14 - Administ	tration Spaces	1	2	3	4	5	N/A		20.00	50%
14.1 Is there of visitors?	a reception area that functions as a security checkpoint for all							Comments	1.00	
1	Very unsatisfactory - No security checkpoint								•	
2	Unsatisfactory - Checkpoint is too small, poor condition									
3	Average - Needs updates or renovations to function well)
4	Satisfactory - Good size, good condition							,		
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply	1	Γ	ı	Т	T	1		<u> </u>	
14.2 Does the	administration area feel welcoming?				4			Comments	1.00	4.00
1	Very unsatisfactory - No welcome space									
2	Unsatisfactory - Too small, poor lighting and									
	transparency, limited informal seating, poor condition									
3	Average - Adequate size and layout, needs updates or									
	renovations to feel welcoming									
4	Satisfactory - Good size and layout, good lighting and									
	transparency, informal seating provided									
5	Very Satisfactory - Generous size and layout, plenty of									
	light and transparency, informal seating provided,									
N/A	excellent condition Does not apply									
	e spaces that require it, does the administration area have	1		l	T	1	1			
1 1/1 /3	e acoustic privacy?			3				Comments	1.00	3.00
1	Very unsatisfactory - No acoustic separations	<u> </u>	l	<u> </u>	1	ı	<u> </u>	Principal's comment: You can hear everything that is		
2	Unsatisfactory - Acoustic separations do not perform							offices even with doors closed.	3 3	
	well									
3	Average - Some acoustic separations function okay, but							Windows in office area are not energy efficient and a	allow for cold /	hot air
4	portions need updates or renovations							to come into the space.		
4 5	Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations									
N/A	Does not apply									
14.4 Are conf	erence rooms easily accessed for public / parent use?	1						Comments	1.00	1.00
1	Very unsatisfactory - Not accessible for public/parent	1					1	Converted old conference room into office.		
0	use									
2	Unsatisfactory - Limited access, no transparency, poor condition, difficult to find									
3	Average - Adequate accessibility, needs updates or									
	renovations to function well									
4	Satisfactory - Good accessibility, good transparency,									
	good size and condition									
5	Very Satisfactory - Excellent accessibility, excellent									
N/A	transparency, generous size, excellent condition									
IV/A	LINES NOT ANNIV									